# Technical Conference on the NIST Federal Building and Fire Safety Investigation of the World Trade Center Disaster

Project #4: Investigation of Active Fire Protection Systems Suppression Systems Sub-task (NCSTAR 1-4B)

**September 14, 2005** 

Mark Hopkins, P.E.
John Schoenrock, P.E.
Edward Budnick, P.E.

HUGHES ASSOCIATES, INC.

**FIRE SCIENCE & ENGINEERING** 

3610 Commerce Drive, Suite 817, Baltimore, MD 21227-1652

Phone:410-737-8677 Fax:410-737-8688

Web Site: www.haifire.com



#### Purpose:

Investigate the performance of the active fire protection systems in WTC 1, 2 and 7 and their role in fire control, emergency response, and fate of occupants and responders.



#### Scope:

Evaluation of the design, installation and performance of the automatic sprinkler systems, the pre-connected hoses, the standpipe systems, and the associated water supply(s) for WTC 1, 2 and 7.



#### Objectives:

- Documentation of design and installation and comparison to applicable codes (Task 1)
- Documentation of design and capacity of water supply (Task 2)
- 3) Identification and documentation of differences in design among WTC 1, 2 and 7 (Task 3)
- Documentation of normal and fully functional systems for fire control (Task 4)
- 5) Documentation of performance of systems in WTC 1, 2 and 7 on September 11, 2001 (Task 5)



#### **General Approach:**

- □ Literature review
  - Public domain
  - Document Resource Center
  - Retrieval and control
- Reconstruction of Systems
- Hydraulic analyses
  - Baseline
  - Fire incident scenarios
  - September 11, 2001
- ☐ Comparison with installation standards
  - NFPA 13
  - NFPA 14



### **Limitations and Assumptions:**

- ☐ Limited detail
- Unavailable documents
- □ Differences in documentation
- □ Documentation of systems on September 11th




### **Task 1: Installed Fire Suppression Features in WTC 1 and 2**

Automatic fire sprinkler systems essentially throughout
☐ Sub-grade systems installed during original construction
☐ Tower systems retrofit installed in 2 phases
☐ Individual system per floor in towers
Standpipe and pre-connected hose systems throughout
☐ Pre-connected Class III hose stations in each stairway
Pre-connected Class III hose stations in corridors and certain tenant
spaces
Special hazard fire suppression systems
☐ Halon 1301 total flooding systems
☐ Pre-action sprinkler systems
☐ Dry chemical systems
☐ Steam smothering systems
☐ Carbon dioxide systems




Ti S





### Task 1: Fire Department Connections and Sub-Grade Infrastructure for WTC 1 and 2





### Task 2: Evaluation of the Water Supply

Source – NYC Distribution System

Maintained at average steady state pressure of 50 psi

Data

☐ Static: 50 psi

☐ Residual: 11 psi

☐ Flow: 150,000 gpm




### Task 2: NYC Water Distribution System Supply to WTC 1 and 2

#### Legend

- •Red 20" Plaza Loop
- Orange 16"
   Connection to
   Distribution System
- •Blue 12" Cross-Connection Main for Plaza
- •Green 8" Feed Mains for Standpipe and Sprinkler Systems
- •Cyan -

Continuation of Distribution System





### **Task 2: Method of Analysis**

- □ Hydraulic analysis using HASS Hydraulic Analyzer of Sprinkler Systems Program
- □ Determination of delivered densities and areas of coverage
- ☐ Assessment of primary and secondary water supplies
- Determination of water supply duration



### Task 2: Hydraulic Node Representation for Primary Water Supplies (Storage Tanks) in WTC 1 and 2



